



State of Utah

JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

Department of Administrative Services

D'ARCY DIXON PIGNANELLI  
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN  
Director

## MEMORANDUM

Date: 15 June 2006

To: Contractors

From: Rick James, DFCM

Reference: Heber M. Wells Building Remodel  
DFCM Project No.06187310

Subject: **Addendum No. 1**

Addendum	1 page
A/E Addendum Attachment	19 pages
<u>Drawings (Large Format – Separate Attachment)</u>	<u>3 pages</u>
<b>Total</b>	<b>23 pages</b>

---

***Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in this Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.***

1.1 Schedule Changes : This addendum does not change the schedule.

1.2 See the Attached Addendum information from the A/E design team.

End of Addendum

# addendum 001

project:	DFCM Heber Wells Bldg Remodel
project no.:	05310
date:	June 15, 2006
owner:	
bid date:	06/20/2006
bid time:	03:00 PM
no. pages:	18

This Addendum shall be considered part of the Contract Documents and Project Manual for the above mentioned project as though it had been issued at the same time and shall be incorporated integrally therewith. Where provisions of the following supplementary data differ from those of the original Contract Documents and Project Manual, the Addendum shall govern and take precedence.

## General Clarifications:

### See also attached Mechanical and Electrical Addendum

**1.1** The type of construction barricade is to be designed by the contractor. It should take into consideration the local building codes for fire, egress, lighting etc. It should be coordinated with the existing conditions including the offices that are to remain open. It is not the Architect's responsibility to design this system.

**1.2** Typical activities that are to be scheduled after hours (weekends, nights etc.) include but are not limited to the following:

- a. Demolition.
- b. Steel erection.
- c. Concrete work.
- d. Fire proofing spray.
- e. Welding

**1.3** All of the artwork, furniture, with the exception of the fixed tables in the existing breakroom will be removed by the owner.

**1.4** The loading dock area that was discussed at the site as possible location for concrete delivery cannot be used. The slab in this area has a load restriction.

**1.5** The Third South location for the concrete delivery can be used if done during off hours. The existing pavers will need to be protected and the doors can be locked down to avoid interference by the public. This will need to be coordinated with the DFCM in the building.

**1.6** Patch the holes in the existing GRC Panels that will be exposed for the new floor plan.

**1.7** The projector screen shown on Sheet AE122 shall be 60"wide x 80"high.

## Drawings

<u>Item</u>	<u>Description</u>
-------------	--------------------

1.8	Sheet AE102 - Replace this sheet with attached drawing. Revise Hearing Room
-----	---

	06. See revised Sheet AE 503. Reverse door swings for doors 01 and 05. Note revised furniture layout. See Electrical Addendum for power outlet revisions. Wall Types B and C should refer to Detail A5 on Sheet AE501. There is not any fire safing in the walls in this project. The owner has asked for the exterior vertical blinds to be replaced with the specified horizontal blinds. Field verify sizes of exterior window system. Doors 16, 17, 18, 19, 20 and 21 all should be Hardware Group 1. See attached Door and Frame Schedule.
1.9	<b>Sheet AE121</b> - Replace this sheet with attached drawing. Revise lighting layout. Recessed can lights have been changed to 2' x 2' fixtures. See Electrical Addendum.
1.10	<b>Sheet AE503</b> - Replace this sheet with attached drawing. The steel bars called out in Detail C5 are all to be stainless steel. This bar will be exposed.
1.11	<b>Sheet S201</b> - Clarification notes: a. All edges of the opening need the edge tie-in detail (3/S501). Where there is existing concrete on the bridge that connects to existing concrete elsewhere, the detail is not required. b. All of the existing beams, without existing concrete, need the studs per detail 5/S501. c. The maximum load the main floor structure can have is 80psf and a 2000lb point load. These loads cannot be applied at the same time. See attached sketch for the jacking loads. These jacking loads must be shored down through lower floors until the load is below the acceptable limit stated above. d. The 'N' reference for the deck is incorrect. It should be 2" W deck as called out in the Specs and General Structural Notes.

#### Specifications

<u>Item</u>	<u>Description</u>
1.12	<b>Section 03310 Concrete Work</b> Subsection 2.3 D. 7c. The slump must be site verified prior to addition of the plasticizer.
1.13	<b>Section 11132 Projection Screens Part 2 - Products 2.2 C. 9.</b> The size of the viewing surface shall be 60"wide x 80"high

#### Details

<u>Item</u>	<u>Description</u>

#### Approvals

In addition to the manufacturers called out in the contract documents, the following manufacturers, trade names and products are acceptable with the provisions that they shall completely satisfy every requirement of the drawings, specifications, and all addenda, and shall conform to the design, quality and standards specified, established and required for the complete and satisfactory installation and performance of the building and all its respective parts. Any costs incurred due to the use of the following manufacturers shall be paid by the contractor.

<u>Section</u>	<u>Material</u>	<u>Manufacturer</u>	<u>Action</u>
07811	Sprayed Fire-Resistive Materials	South West Fire Proofing Products	Approved
08710	Door Hardware - Stops	Hagar	Approved


End of Addendum # 001


cc :

# DOOR AND FRAME SCHEDULE

DOOR NUMBER	DOOR					FRAME					HARDWARE GROUP	LABEL (HRS)	NOTES
	DOOR TYPE	NEW / EXG / REL	SIZE			MATERIALS	NEW / EXG / REL	ELEVATION	MATERIAL	DETAILS			
			WIDTH	HEIGHT	THICK								
01	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	2	N/R	SECURE DOOR ACCESS
02	NOT	USED											
03	NOT	USED											
04	NOT	USED											
05	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F3	HM	D6	2	N/R	SECURE DOOR ACCESS
06	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F3	HM	D6	1	N/R	
06 A	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F3	HM	D6	1	N/R	
07	NOT	USED											
08	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F1	HM	D3,D6	1	N/R	
09	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	1	N/R	
10	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	1	N/R	
11	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	1	N/R	
12	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F3	HM	D6	1	N/R	
13	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F3	HM	D6	1	N/R	
14	NOT	USED											
15	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	1	N/R	
16	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	1	N/R	
17	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F4	HM	D3,D6	1	N/R	
18	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F1	HM	D3,D6	1	N/R	
19	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F4	HM	D3,D6	1	N/R	
20	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	1	N/R	
21	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F2	HM	D3,D6	1	N/R	
22	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F3	HM	D6	1	N/R	
23	D1	N	3'-0"	7'-0"	1-3/4"	SCWD	N	F3	HM	D6	1	N/R	

APPENDIX # 1 ITEM 1.8





**SPECTRUM  
ENGINEERS**

## Addendum

**Job:** Heber Wells  
**Job Number:** 20050373  
**Date:** June 14, 2006

---

### MECHANICAL – DIV 15

#### DRAWINGS

##### MH101

1. Diffusers served by VR-1 should supply 735 cfm each.
2. VR-24 has been added near VR-2 to supply two of the diffusers previously supplied by VR-2.
3. Appropriate duct modifications have been resized. See drawings MH-101-R1-1 and MH-101-R1-2.

##### MH102

4. Delete new return air opening to shaft. Change note 3 to read, "Existing return air openings to remain."
5. Duct return air grill above ceiling and through wall into return air ceiling plenum with return air sound boot in rooms Office 17, Sm. Conf. 18, and Office 19.
6. Change diffuser supply in Sm. Conf. 18 to 610 cfm.
7. Change diffuser supply in Office 20 to 500 cfm.
8. Change diffuser supply in Office 22 to 405 cfm.
9. Change diffuser supply in Storage/Files 23 to 55 cfm. Locate return air grille in this room inside room walls.
10. Change diffuser supply in Storage/Files 13 to 250 cfm.
11. Change diffuser supply in Open Office 03, Open Office 04, and Open Office 05 to 250 cfm. Change return air grilles in these areas to 650 cfm.
12. Add supply diffuser in Conference Room 08. See drawing MH-102-R1-1.
13. Add supply diffuser in Break 14. See drawing MH-102-R1-1.
14. Change note number 6 to read "Install new fire/smoke damper in new section of exhaust duct and shaft wall penetration."
15. Add exhaust grille above new copy machine location, move grille to relocated copy machine. See MH-102-R1-2.

##### MP101

16. VR-24 has been added and shown with corresponding thermostat. See drawing MP-101-R1-1.
17. Thermostats for VAVs have been shown. See drawings MP-101-R1-1 and MP-101-R1-2.
18. Pipe sizes have been shown. See drawings MP-101-R1-1 and MP-101-R1-2.
19. Add note number 4, "Set at 12.8 gpm." See drawing MP-101-R1-3.

##### MP102

20. Change VR-6 to VR-15. VR-6 had not been shown in correct location. Locate VR-6 and VR-15 in appropriate locations as shown on MH-102.
21. Connect VR-6 to main piping loop.

22. Add thermostat to northeast wall of Conference Room 08 near door and connect to VR-6.

ME501

23. See updated variable volume reheat box schedule on drawing ME-501-R1-1.  
24. SWR-1 model is 535 by EH Price.

## PRIOR APPROVALS

Approval of equipment from catalog information indicated brand name and general characteristics are acceptable to the Engineer, but does not relieve the Contractor of the responsibility of providing equipment and accessories as specified unless specific mention of departments from specifications was made in the submittal and acknowledged in writing by the Engineer. Quantities and dimensions are not checked. We are retaining one set of submittal data for our files.

<u>SECTION</u>	<u>ITEM</u>	<u>MANUFACTURER</u>	<u>COMMENT</u>
15820	Fire smoke dampers	Pottorff	Approved
15820	Manual volume dampers	Pottorff	Approved

## ELECTRICAL – DIV 16

---

### GENERAL ITEMS

1. The Division 16 Unit Price Bid Form is attached to this addendum and shall be completed by the apparent low bidder prior to being awarded the contract. The unit prices given shall be guaranteed for the duration of the project, and is the same for adds or deducts.

### SPECIFICATIONS

#### SECTION - 16511

1. Paragraph 2.4.B: Add the following paragraphs:
9. Input Power: When operated with a 4' T8, high-output (3100 initial lumens), extended performance lamp the maximum input power is as follows:
- a. 1-lamp: 25 watts.
  - b. 2-lamps: 49 watts.
  - c. 3-lamps: 72 watts.
  - d. 4-lamps: 94 watts.
10. Manufacturers: Provide products in conformance with the requirements of the contract documents manufactured by one of the following.
- a. Advance Transformer CO, "IOP" Series
  - b. Osram/Sylvania, "PSX" Series
  - c. General Electric Co., "Ultra Start" Series.

### DRAWINGS



**EP-102**

1. Poke-through outlets have been adjusted to coordinate with latest furniture layout. Refer to attached revision drawing.
2. Receptacles and data outlets have been added for additional copier. Refer to attached revision drawing.

**EL-101**

1. All type DF-25 type light fixtures are to be replaced with P3-2 type light fixtures on a location for location basis, including those indicated to be connected to emergency circuits.

**EL-601**

1. Fixture Schedule:
  - A. Add the following sentences to the fixture schedule heading:  
Fluorescent fixtures with 4' T8 lamps use 32 watt 3100 initial lumen lamps with .71 ballast factor electronic ballast. Lamps: OSI "XPS" series, Philips "ADV" series, GE "T8 ultra high lumen". Ballasts: Advance "IOP" series, OSI "Prostart PSX", GE "Ultrastart" series.
  - B. Delete fixture type DF-25 from fixture schedule.
  - C. Add the following fixture type to the fixture schedule:

MARK	CHARACTERISTICS	LAMP	WATTS	VOLTS
P3-2	2X2 9-cell lay-in; semi-specular silver louvers, static	2-F31T8 RE835	65W	120/277

MANUFACTURER	CATALOG NUMBER
Lithonia	2PM3NGB-2U316-9LD-MVOLT-TUBRHP-2R
Daybrite	2P3GS231U6-33SL-UNV-1/2-EB-SPEC
Metalux	2EP3GX-2U6S33I-UNV-PROGRAM START
Columbia	P4D24-232U6G-LD33-S-EB8LHPRUNV
LSI	N2PG9 2U32 FD SSO10PS UE
Lightolier	DPS2G9LS26U-U-SOP

2. Subject to compliance with the requirements of the project documents, the following lighting fixtures have been reviewed and are found acceptable to be used on this project:

TYPE	MANUFACTURER	CATALOG NUMBER
CM-14	Finelite Peerlite	S8-PW-XX-2T8-SC-91W-UNV-FA-FE 10CRM4-2-32-40/60-SSB-XX-R12-120/277-GEB10-SC-L/LP-F1/XX-ACG
CM-14d	Finelite Peerlite	S8-PW-XX-2T8-DC-91W-UNV-FA-FE 10CRM4-2-32-40/60-SSB-XX-R12-120/277-GEB10-DCT-L/LP-F1/XX-ACG
CM-15	Finelite Peerlite	S5WM-XX-2T8-SC-SPEC-UNV-FE CRW7-2-32-WHR-4FT-R4-120/277-GEB10-L/LP
OX-4	Primus	PL-R-LED-1/2-C-24-X

3. Fixture type TX-1 shall be a Visa CP3026-MOD-277V-CB-48" CA/LLL. Bidders are instructed to use \$2840.00 per fixture as the contractor allowance.

**EY-102**

1. Add one control module, relay and duct smoke detector to control fire smoke damper(s). Provide 120V circuit connected to 2LD2-17. Refer to mechanical sheet MH-102 for damper locations.
2. Change 15 candela fire alarm speaker/strobe to 30 candelas in Conference Room 08, centered on north wall. Remove fire alarm speaker/strobe from Office 09.
3. Change 30 candela fire alarm speaker/strobe to 75 candelas in Break Room 07.
4. Add 15 candela fire alarm speaker/strobe in Small Conference Room 18, centered on west wall.

#### **ET-601**

1. On Detail 7 add a Radio Design labs line mixer ST-MX3 on the 2 aux lines after the isolation transformers.
2. On The Sound Symbol Legend the 'Proc' is to be a Biamp Nexia CS.

#### **END OF ADDENDUM**

## VARIABLE VOLUME REHEAT BOX SCHEDULE


SYMBOL	MANUFACTURER	MODEL	INLET BOX SIZE	BOX PRESS. DROP	CFM			NC LEVELS @2" S.P.			COIL			MIN. ROWS	MIN. FINS.	COMMENTS
					COOLING	HEATING	MINIMUM	AIR	RAD	DEG. F	LAT	GPM	P.D.			
VR-1	PRICE	SDV	16	0.22	2205	970	665	28	31	99.9	4.2	0.21	24x18	1	8	1)2)3)4)5)6)8)
VR-2	PRICE	SDV	12	0.19	1110	350	350	27	27	98.0	1.5	0.18	16x15	1	8	1)2)3)4)5)6)7)
VR-3	PRICE	SDV	12	0.19	1110	350	350	27	27	80.0	0.9	0.18	16x15	1	8	1)2)3)4)5)6)7)
VR-4	PRICE	SDV	12	0.21	1214	365	365	28	28	97.4	1.5	0.20	16x15	1	8	1)2)3)4)5)6)7)
VR-5	PRICE	SDV	9	0.19	830	250	250	26	24	98.7	1.1	0.18	14x12.5	1	8	1)2)3)4)5)6)7)
VR-6	PRICE	SDV	6	0.18	270	120	85	19	18	99.0	0.5	0.08	12x8	1	8	1)2)3)4)5)6)7)
VR-7	PRICE	SDV	6	0.18	270	120	85	19	18	99.0	0.5	0.08	12x8	1	8	1)2)3)4)5)6)7)
VR-8	PRICE	SDV	10	0.23	920	340	280	25	24	99.8	1.5	0.22	14x12.5	1	8	1)2)3)4)5)6)7)
VR-9	PRICE	SDV	7	0.14	370	120	115	23	21	99.0	0.5	0.09	12x10	1	8	1)2)3)4)5)6)7)
VR-10	PRICE	SDV	7	0.14	370	120	115	23	21	99.0	0.5	0.09	12x10	1	8	1)2)3)4)5)6)7)
VR-11	PRICE	SDV	8	0.19	570	195	175	23	22	99.7	0.8	0.18	12x10	1	8	1)2)3)4)5)6)7)
VR-12	PRICE	SDV	9	0.14	680	205	205	27	22	95.0	0.8	0.13	14x12.5	1	8	1)2)3)4)5)6)7)
VR-13	PRICE	SDV	8	0.19	570	180	175	23	22	99.4	0.8	0.18	12x10	1	8	1)2)3)4)5)6)7)
VR-14	PRICE	SDV	8	0.20	585	225	180	23	23	100.0	1.0	0.19	12x10	1	8	1)2)3)4)5)6)7)
VR-15	PRICE	SDV	6	0.18	270	120	85	19	18	99.0	0.5	0.08	12x8	1	8	1)2)3)4)5)6)7)
VR-16	PRICE	SDV	6	0.20	310	120	95	21	20	99.0	0.5	0.10	12x8	1	8	1)2)3)4)5)6)7)
VR-17	PRICE	SDV	8	0.17	520	170	160	22	22	100.0	0.7	0.16	12x10	1	8	1)2)3)4)5)6)7)
VR-18	PRICE	SDV	9	0.16	740	225	225	27	23	80.0	0.6	0.15	14x12.5	1	8	1)2)3)4)5)6)7)
VR-19	PRICE	SDV	16	0.26	2500	750	750	29	32	80.0	1.9	0.25	24x18	1	8	1)2)3)4)5)6)7)
VR-20	PRICE	SDV	12	0.22	1250	375	375	28	28	80.0	1.0	0.21	16x15	1	8	1)2)3)4)5)6)7)
VR-21	PRICE	SDV	8	0.18	535	165	165	22	22	80.0	0.5	0.17	12x10	1	8	1)2)3)4)5)6)7)
VR-22	PRICE	SDV	12	0.24	1320	515	400	28	29	99.8	2.2	0.23	16x15	1	8	1)2)3)4)5)6)7)
VR-23	PRICE	SDV	8	0.18	535	165	165	22	22	80.0	0.5	0.17	12x10	1	8	1)2)3)4)5)6)7)
VR-24	PRICE	SDV	16	0.22	2200	660	660	28	31	99.4	2.9	0.21	24x18	1	8	1)2)3)4)5)6)7)

- (1) ENTERING AIR AT 52 DEG F @ 4500 FT. ELEVATION.
- (2) GPM BASED ON 180 DEG F ENTERING WATER TEMPERATURE, 160 DEG F LEAVING WATER TEMPERATURE
- (3) COIL MAXIMUM WATER P.D. AT 3.0 FT. ' MAX. AIR P.D. AT 0.10".
- (4) MAXIMUM N.C. LEVEL AT 2.0" S.P. - AIR 36, RAD., 30 UNLESS OTHERWISE NOTED.
- (5) NC LEVELS ARE BASED ON 5 FT. LINED DUCT, 100b ROOM ATTENUATION AND AN AVERAGE LAY-IN CEILING WITH STC 34-40 RATING.
- (6) COIL BASED ON PACE TYPE HW COILS.
- (7) PIPE SIZE TO REHEAT COILS IS 3/4"
- (8) PIPE SIZE TO REHEAT COILS IS 1"




**SPECTRUM ENGINEERS**  
 175 South Main Street, Suite 300  
 Salt Lake City, Utah 84111  
 801-328-5151 800-678-7077  
 FAX 801-328-5155  
 www.spectrum-engineers.com  
 © 2006 Spectrum Engineers, Inc.

REFERENCE: ME-501	PROJECT
ISSUE:	HEBER M. WELLS BUILDING REMODEL
DATE: 06.13.06	SHEET TITLE
PROJ NO: 20050737	VAV SCHEDULE
DRAWN BY: EWL	SCALE
CHECKED BY: JTJ	NO SCALE
	ME-501-R1-1



**MH-101-R1-1**

P: \2005\20050373\1Drawings\Sheet\73MH-101-R1-2.dwg Last Plotted: 06/13/2006 @ 11:34 By: ewl



**SPECTRUM  
ENGINEERS**  
175 South Main Street, Suite 300  
Salt Lake City, Utah 84111  
801-328-5151 800-678-7077  
FAX 801-328-5155  
www.spectrum-engineers.com  
© 2006 Spectrum Engineers, Inc.

REFERENCE: MH-101		PROJECT	
ISSUE:		HEBER M. WELLS BUILDING REMODEL	
DATE: 06.13.06		SHEET TITLE	
PROJ NO: 20050737		MAIN LEVEL MECHANICAL HVAC PLAN	
DRAWN BY: EWL		SCALE	MH-101-R1-2
CHECKED BY: JTJ		1/8"=1'-0"	



175 South Main Street, Suite 300  
Salt Lake City, Utah 84111  
801-328-5151 800-678-7077  
FAX 801-328-5155  
www.spectrum-engineers.com  
© 2006 Spectrum Engineers, Inc.

**ISSUE:**

DATE: 06.13.06

PROJ NO: 20050737

DRAWN BY: EWL

CHECKED BY: JTJ

## HEBER M. WELLS BUILDING REMODEL

**SHEET TITLE**


## SECOND LEVEL MECHANICAL HVAC PLAN

SCALE

$$1/8'' = 1' - 0''$$

**MH-102-R1-1**

P:\2005\20050373\Drawings\Sheet\73MH-102-R1-2.dwg Last Plotted: 06/13/2006 @ 14:15 By: ewl



**SPECTRUM  
ENGINEERS**

175 South Main Street, Suite 300  
Salt Lake City, Utah 84111  
801-328-5151 800-678-7077  
FAX 801-328-5155  
www.spectrum-engineers.com  
© 2006 Spectrum Engineers, Inc.

REFERENCE: MH-102

ISSUE:

DATE: 06.13.06

PROJ NO: 20050737

DRAWN BY: EWL

CHECKED BY: JTJ

PROJECT

**HEBER M. WELLS BUILDING REMODEL**

SHEET TITLE


**SECOND LEVEL MECHANICAL HVAC PLAN**

SCALE

1/8"=1'-0"

**MH-102-R1-2**

P: 2005\20050373\1Drawings\Sheet\73MP-101-R1-1.dwg Last Plotted: 06/13/2006 @ 11:33 By: ewl



**SPECTRUM  
ENGINEERS**

175 South Main Street, Suite 300  
Salt Lake City, Utah 84111  
801-328-5151 800-678-7077  
FAX 801-328-5155  
www.spectrum-engineers.com

© 2006 Spectrum Engineers, Inc.

REFERENCE: MP-101

ISSUE:

DATE: 06.13.06

PROJ NO: 20050737

DRAWN BY: EWL

CHECKED BY: JTJ

PROJECT

**HEBER M. WELLS BUILDING REMODEL**

SHEET TITLE

**MAIN LEVEL MECHANICAL PIPING PLAN**

SCALE

1/8"=1'-0"

**MP-101-R1-1**



P:\2005\20050373\1Drawings\Sheet\73MP-101-R1-2.dwg Last Plotted: 06/13/2006 @ 11:32 By: ewl



**SPECTRUM  
ENGINEERS**

175 South Main Street, Suite 300  
Salt Lake City, Utah 84111  
801-328-5151 800-678-7077  
FAX 801-328-5155  
www.spectrum-engineers.com

© 2006 Spectrum Engineers, Inc.

REFERENCE:	MP-101
ISSUE:	
DATE:	06.13.06
PROJ NO:	20050737
DRAWN BY:	EWL
CHECKED BY:	JTJ

PROJECT

**HEBER M. WELLS BUILDING REMODEL**


SHEET TITLE

**MAIN LEVEL MECHANICAL PIPING PLAN**

SCALE

1/8"=1'-0"

**MP-101-R1-2**



# **SHEET KEYNOTES**

1. CONNECT TO EXISTING HOT WATER SUPPLY AND RETURN MAIN LINES.
2. INSTALL 3-WAY CONTROL VALVE.
3. INSTALL 2-WAY CONTROL VALVE.
4. SET AT 12.8 GPM.



**SPECTRUM  
ENGINEERS**

175 South Main Street, Suite 300  
Salt Lake City, Utah 84111  
801-328-5151 800-678-7077  
FAX 801-328-5155  
www.spectrum-engineers.com  
© 2006 Spectrum Engineers, Inc.

REFERENCE: MP-101

ISSUE:

DATE: 06.13.06

PROJ NO: 20050737

DRAWN BY: EWL

CHECKED BY: JTJ

PROJECT

**HEBER M. WELLS BUILDING REMODEL**

SHEET TITLE


**MAIN LEVEL MECHANICAL PIPING PLAN**

SCALE

1/8"=1'-0"

**MP-101-R1-3**

P:\2005\20050373\1Drawings\Sheet\Addendum\73EP-102-R1-1.dwg Last Plotted: 06/13/2006 @ 14:07 By: rbk



**SPECTRUM  
ENGINEERS**

175 South Main Street, Suite 300  
Salt Lake City, Utah 84111  
801-328-5151 800-678-7077  
FAX 801-328-5155  
www.spectrum-engineers.com  
© 2006 Spectrum Engineers, Inc.

REFERENCE:	EP-102
ISSUE:	ADDENDUM
DATE:	06/13/06
PROJ NO:	20050373
DRAWN BY:	TNB
CHECKED BY:	RBK

PROJECT **DFCM PROJECT #06187310**  
**HEBER M. WELLS**  
**BUILDING REMODEL**

SHEET TITLE **SECOND LEVEL POWER PLAN**

SCALE  
1/8"=1'-0"

**EP-102-R1-1**

HEBER M. WELLS REMODEL  
DIVISION 16 UNIT PRICE BID FORM

DIVISION 16 - ELECTRICAL UNIT PRICE BID FORM

UNIT PRICES

1. Lighting fixtures

- a. **Lighting fixtures:** Guarantee unit prices for each item listed. Change order (add or deduct) amounts for lighting fixtures (excluding lamps, sales tax, and installation) shall be the prices listed below multiplied by the quantities added or deducted.

<u>Type</u>	<u>Manufacturer</u>	<u>Unit Price</u>
CM-14		
CM-14d		
CM-15		
E3-1		
E3-2		
GS-2		
GS-3		
OX-4		
P3-2		
P3-6		
P3-8		
P3-12		
SC-1		
SC-3		
TX-1		
UC-10		
UC-11		

- b. **Lighting fixture installation:** Guarantee unit prices for each item listed. Change order (add or deduct) amounts for installation of lighting fixtures (excluding fixtures, lamps, and sales tax) and including 30' of typical branch wiring shall be the prices listed below multiplied by the quantities added or deducted.

<u>Type</u>	<u>Manufacturer</u>	<u>Unit Price</u>
CM-14		
CM-14d		
CM-15		
E3-1		
E3-2		
GS-2		
GS-3		
OX-4		
P3-2		
P3-6		
P3-8		
P3-12		
SC-1		
SC-3		
TX-1		